10/29/91 Settled on Corner: M & L


#653204

1/4 Corner South 1/4 32 Salem 106-15
North 1/4 5 Rock Dell 105-15

Set by John Ball 10-1853

40.00 Set post and drove charred stake for quarter Section Corner. Built mound with trench per instructions Planted SE 1/4 Osage Orange, NE Apple Seed.

9-22/23-1981 : S. 1/4 Cor 32 : Dug from the traverse road, set on line from CIM @ SW 32 to 5/8" rod set back at SE 32, as follows:



by 5' deep to clay. Conditions only fair. Found nothing. Digging to corn midway and also

2640' from SW 32. Should dig a little farther West to cover doubling 1/16 fence West.

10/29/91 Set corner M&L from CIM @ SW 32 to Reread at SE 32 for Kleinschmidt survey in Sec 32. Will place monument when we can get to it.